

Barbizon Charlotte

Quote # Brevard HS 2014.02.010.017PS  
2/10/2014

Item	Qty	Mfg.	Description
<b>Section I - Dimming System</b>			
1.0			
	1	ETC	Unison Echo Relay Panel
	2	ETC	24 single-pole relays; 24 single-pole breakers 120/208V three-phase four-wire plus ground main lug
	2		main Breaker; 120V Single-phase; 200a; 22kaSCCr
	2		Surface-mount door for 120V Echo Relay Panel
	1		Ethernet interface
			Electrical Contractor
			Set and Energize all Barbizon provided Equipment
			Pricing
			Labor
			Lift/Ladder/Scaffold
			Misc Allowance
2.0			<b>Section II - Control System</b>
	1	ETC	<b>ETC ION 2000 Control Console</b> with 2x20 Fader Wing
	1		19" LCD Monitor
	1		19" LCD Touchscreen Monitor
	1	CDW	Monitor dust cover
	1	Lex	25' DMX Control Cable
	1	Lex	25' Net Control Cable
	1	Littlite	Console Worklights
	1	CDW	Console UPS
	1	CDW	Console Plug Strip
	1	Barbizon	<b>Wireless Access and Remote Control</b> All kits include the iDevice listed, protective rubberized case, screen protector, iRFR app, airport express
	5	ETC	<b>ETC Control Plug-in Station</b> with 1-Net input - pipe mountec
	2	ETC	<b>ETC Control Plug-in Station</b> with 1-Net input - recess mounted
	4	ETC	<b>ETC Portable 2-port DMX Gateway</b> with c-clamp and safety cable
	4	Lex	25' Net Control Cable
			<b>Control Rack:</b> to include the following: Middle Atlantic Equipment Rack - 12 space wall mounted rack with front door
	1	Middle Atlantic	Rack with rear door
	1	Middle Atlantic	Front Door
	1	Dell	Dell 24-port POE Switch
	1	Hubbell	Hubbell 24-port CAT5 Patch Panel
	1	Middle Atlantic	Middle Atlantic Brush Grommet Panel
	1	Pathway	Pathport Octo 8-port Node, rear RJ45 EtherCon
	1	Pathway	Pathway Connectivity 8-way Opto-splitter
	24		Ethernet Patch Cables
	1	Middle Atlantic	Middle Atlantic 1000VA Rackmounted Un-interruptible Power Supply
	1	Middle	Lot of cable management devices, black panels and miscellaneous hardware
	1		Control Wire Allowance

Barbizon Charlotte

3.0			<b>Section III - Architectural Controls</b>
4.0			<b>Section IV - Power Distribution</b>
1	ETC		ETC Connector Strip - 42'-0" with 10-18" pigtails with 20A 2P&G connectors wired to 20-20A circuits
1			ETC Connector Strip - 42'-0" with 7-18" pigtails with 20A 2P&G connectors wired to 14-20A circuits
1			ETC Connector Strip - 42'-0" with 7-18" pigtails with 20A 2P&G connectors wired to 14-20A circuits
1			ETC Connector Strip - 42'-0" with 7-18" pigtails with 20A 2P&G connectors wired to 14-20A circuits
1			ETC Connector Strip - 42'-0" with 3-18" pigtails with 20A 2P&G connectors wired to 12-20A circuits
4			ETC Surface Mounted Outlet Box with 2-panel mounted 20A 2P&G connectors -- Down
2			ETC Surface Mounted Outlet Box with 3-panel mounted 20A 2P&G connectors -- Up Stage
5.0			<b>Section V - Fixtures and Accessories</b>
			<b>LED</b>
18	ETC		ETC 19° Source Four Lustr+ LED Ellipsoidal with c-clamp, color frames, safety cable and Lustr+ Light Engine with shutter barrel 2P&G connector, c-clamp, diffuser and pattern holder
18	ETC		19-degree Enhanced Definition Lens Tube with color frame
39	Peak Trading		Safety Cable
18	ETC		ETC 26° Source Four Lustr+ LED Ellipsoidal with c-clamp, color frames, safety cable and Lustr+ Light Engine with shutter barrel 2P&G connector, c-clamp, diffuser and pattern holder
0	ETC		19-degree Enhanced Definition Lens Tube with color frame
18	Peak Trading		Safety Cable
			ETC Selador Desire D40 Lustr+ LED Wash Light with c-clamp, safety cable, lenses and Edison
24	ETC		Fixture with lens, power lead and Edison connector
24	ETC		C-clamp
24	Peak Trading		Safety Cable
24	ETC		TBD Lenses (x4)
			ETC Source Four Lustr+ LED Cyc with cyc lens, c-clamp, color frames, safety cable and 2P&G
9	ETC		Lustr+ Light Engine with shutter barrel 2P&G connector, c-clamp, diffuser and pattern holder
9	ETC		Cyc Lens
9	Peak Trading		Safety Cable
			<b>Followspot</b>
	Strong		Strong Canto 1200 Followspot with lamp and stand.
1	Strong		Followspot with stand and bommerang
1	Phillips		1200W Lamp
1			Connector-installed
			<b>Automated Luminaire</b>
8	Elation		Platinum Spot 5R Pro
8			lamp
0	Light Source		Mega Claw-clamp
			<b>Accessories</b>
6	ETC		Spare D40 Lenses
12	City Theatrical		City Theatrical A-size Pattern Holder
10	ETC		ETC 19° Lens Tube
8	ETC		ETC 26° Lens Tube
			<b>Control Cable</b>
4	Lex		5' Net Control Cable
50	Lex		15' DMX Control Cable
4	Lex		25' DMX Control Cable
1	Lex		50' DMX Control Cable
			<b>Jumper Cable</b>
10	Lex		5' Jumper Cable with 2P&G connectors
10	Lex		10' Jumper Cable with 2P&G connectors
4	Lex		25' Jumper Cable with 2P&G connectors
2	Lex		50' Jumper Cable with 2P&G connectors
8	Lex		20A Twofer with 2P&G connectors
			<b>Expendables</b>
4	ProTape		2" Roll of Black Gaffers Tape
1			3,000' of Black Tie-line
			<b>Fixture Installation</b> to include:
			<b>Prep, hang and focus of 120 fixtures.</b>
1			3 technicians for 3 days @ \$500/day
1			Lift/Ladder/Scaffold
1			Misc Allowance

Barbizon Charlotte

6.0			<b>Section VI - House Lights</b>
7.0			<b>Section VII - Motorized Rigging</b>
	1	ETC	<b>ETC Prodigy P1500E Hoist</b> to include powerhead, compression tube, wire
		ETC	Connector Strip - 46'-0" with 16-panel mounted 20A 2P&G connectors wired
		ETC	Cable Management to include flat cables, terminal boxes and all other
			45'-0" 1.5" schedule 40 Pipe Batten
		ETC	<b>ETC Prodigy Power and Control Outlet Box</b> with 1-Power Connectors, 1-
		ETC	<b>ETC QuickTouch 4 Controller</b>
		ETC	Hand Held Remote
		ETC	Emergency Stop Button
			<b>Installation</b> to include installation of (4) motorized rigging sets
			<u>Pricing</u>
		ETC	ETC Rigging Quote
		ETC	ETC Rigging Quote - QuickTouch Training
		IDPS	Georgia Stage Quote - Prodigy Installation
		IDPS	Georgia Stage Quote - Hardware
		Barbizon	Low Voltage Terminations
			Control Wire Allowance
		Barbizon	Shop Drawings
		Barbizon	Misc allowance
8.0			<b>Section VIII - Rigging, Track and Drapery</b>
	2	SSRC	<b>Fixed Rigging</b>
			<b>6x6 Tormentor</b> to include 1.5" sched. 40 pipe, hanging assemblies and all other necessary
			<b>Rigging Installation</b>
		IDPS	<b>Installation</b> to include installation of fixed rigging, track and drapery.
			<u>Pricing</u>
	1	IDPS	Imagine Quote ### - Pipe Battens, Tormentor, hardware, lifts and installation.
	1		Shop Drawings
	1		Misc allowance
9.0			<b>Section IX - Alternate #2 - Additional Equipment</b>
10.0			<b>Section X - Barbizon Services</b>
	1		System Design
	1		ETCP Certified Supervision
	1		Project Management
	1		Technical Service Training
	1		Technical Service Inspection and Service Agreement
	1		Freight

This quotation is not a contract.

Barbizon Charlotte

Quote # Brevard HS 2014.02.010.017PS

2/10/2014

<b>Equipment</b>	<b>\$ 245,626.88</b>
<b>Labor</b>	<b>\$ 52,794.12</b>
<b>Subtotal</b>	<b>\$ 298,421.00</b>
<b>Sales Tax Rate</b>	<b>6.75%</b>
<b>Sales Tax</b>	<b>\$ 16,579.81</b>
<b>Total</b>	<b>\$ 315,000.81</b>

Thank you for calling on Barbizon for your lighting needs. Should you have any questions about the above quotation,

Paul Strom  
Barbizon Charlotte, Inc.  
Systems Division

**BARBIZON PROJECT MANAGEMENT SERVICES:**

**Project Management Services:** Services include, but are not necessarily limited to the following:

- A. Contractor Coordination** - includes providing information to and answering technical questions for contractors of other trades, primarily the electrical contractor.
- B. On Site Services** - includes making site visits as necessary and required to oversee job progress and answer questions for the owner, owners representative, or contractors.
- C. Progress Meetings** - includes attending jobsite progress meetings as necessary and required to ensure successful completion of the project.
- D. Scheduling** - includes coordinating delivery of equipment as well as scheduling of Barbizon and factory employed service
- E. Documentation** - includes providing submittal drawings, close out information, as well as other documentation as necessary to

**SERVICES:**

- 1 - **Drawings:** Four sets of B size drawings for approval submitted within 4 weeks of receipt of order.
- 2 - **Terminations:** Termination of all low voltage wiring to be done by factory authorized, Barbizon employed engineer. All wire within conduit and the pulling of the wire shall be provided by others.
- 3 - **Turn-On & Training:** The services of a factory authorized, Barbizon employed engineer who shall check the installation, energize the equipment and demonstrate its proper operation. Such services to be supplied on 14 days notice and not to exceed 1 full working day.
- 4 - **Manuals:** Two sets of Operation Manuals
- 5 - **Warranty:** Two year limited warranty on parts and workmanship.
- 6 - **Production:** Productions requires 1-6 weeks for delivery of equipment after receipt of written approval and release.

**PROJECT NOTES:**

- FOB Manufacturer, ground freight allowed (included)
- This quotation does not include installation, except where specifically stated.
- Unless otherwise stated, duties, taxes, fees, if applicable are not included in this quote.
- Submittals are billable upon delivery at 5% of the total order.
- Terms are Net 30 with open account in good standing.
- This quote is based on Barbizon's interpretation of the project.

Orders will only be accepted limited to the bill of materials and/or scope of work detailed.

- This quotation and any accompanying documents are the intellectual property of Barbizon Lighting Company and may not be
- Asbestos remediation, if called for or encountered is not included.
- No Painting or Patching of walls or ceilings.
- No bonding, job permits, or fees have been included.
- Barbizon's standard insurance applies, certificates available upon request.
- Barbizon's standard Terms and Conditions of sale apply.
- This quotation is valid for 30 days. Thereafter it is subject to change without notice.